

## West Seneca Central School District

Ebenezer Building • 900 Mill Road • West Seneca, New York 14224-3082

Telephone: (716) 677-3681 • Facsimile: (716) 674-0152

**Matthew Bystrak** Superintendent of Schools

Joseph M. Farr Superintendent of Buildings & Grounds

September 19, 2022

RE: Winchester-Potters Road Building, at 675 Potters Road

Dear Winchester-Potter Road Building Parents, Guardians and Occupants:

To protect public health, New York State (NYS) recently enacted a new regulation requiring that every public school in New York State test their drinking water for lead. If lead is found at any water outlet at levels above 15 parts per billion (ppb), NYS requires that action be taken to reduce the lead to a level not to exceed 15 parts per billion.

It is vital that schools conduct these tests, as high levels of lead in drinking water can cause health problems. Lead is unusual among drinking water contaminants in that it seldom occurs naturally in water supplies like groundwater, rivers, and lakes. Lead enters drinking water primarily as a result of the corrosion, or wearing away, of materials containing lead in the water distribution system and in building plumbing. These materials include lead-based solder used to join copper pipe, brass, and chrome-plated brass faucets. In 1986, Congress banned the use of lead solder containing greater than 0.2% lead, and restricted the lead content of faucets, pipes and other plumbing materials. However, even the lead in plumbing materials meeting these new requirements is subject to corrosion. When water stands in lead pipes or plumbing systems containing lead for several hours or more, the lead may dissolve into the drinking water.

The West Seneca Central School District, in accordance with legislation signed by the Governor on September 6, 2016, continues on a regular schedule to test our faucets throughout our educational buildings. We continue the process to remediate non-conforming items. We received and opened test reports, September 14, 2022 and have disabled any questionable outlets. The District has tested water sources in the past under the EPA regulations. New York State's new regulations have lowered the acceptable thresholds so at this point, we are conforming to the new regulations. The results and actions taken by the District are as follows:

## **WINCHESTER-POTTERS**

Kitchen Sink #2 – 19.4 ppb, valve off, replacement scheduled Kitchen Sink #3 – 42.9 ppb, valve off, replacement scheduled

Kitchen Kettle #4 – 143 ppb, valve off, replacement scheduled

Sink Room 130 – 97.5 ppb, valve off, replacement scheduled

Sink Room 102 – 23.8 ppb, valve off, replacement scheduled

Sink Room 206 – 29.0 ppb, valve off, replacement scheduled

Sink Room 209 – 88.0 ppb, valve off, replacement scheduled

Sink Room 210 – 56.5 ppb, valve off, replacement scheduled

Winchester-Potters Road Building Page 2

Sink Room 214 – 44.0 ppb, valve off, replacement scheduled Sink Room 216 – 100 ppb, valve off, replacement scheduled 2<sup>nd</sup> Floor Girls' Restroom – 47.3 ppb, valve off, replacement scheduled Room 211 – 26.3 ppb, valve off, replacement scheduled

NOTE #1: All readings are in parts per billion.

NOTE #2: All samples have been taken after the faucets have been dormant for 8-18 hours. The samples are first draw samples which means, the sample is what actually was stored in the faucet in the past 8 -18 hours. Personal/professional good practice advises that anywhere that you get water from a faucet especially at home because your homes are not regulated to the same stringent levels that the schools are, would be to not take first draw water but turn the faucet on for a minimum of 3 seconds before using that water.

In the past few weeks in accordance with regulations, we have tested all of our educational buildings and have taken any corrective actions necessary.

The West Seneca Central School District last conducted testing for lead in the water in 2016. The District will be conducting complete testing for lead on a five-year cycle from this point forward. This current testing was delayed due to a period of time where the buildings were not in use due to COVID-19.

Sincerely,

Joseph M. Farr Superintendent of Buildings and Grounds West Seneca Central School District